

2 100222

MAY 08 1987

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 095-21,569-0000
C N/2 NE, SEC. 28, T 27 S, R 8 W/EX
4620 feet from S section line
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4548

Lease Name Drumright Well # 1-28

Operator: ONEOK Exploration Company
Name & Address P.O. Box 871
Tulsa, OK 74102-0871
918-588-7700

County Kingman 143.98
Well Total Depth 554430 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 276

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Eagle Drilling, Inc. License Number 5380

Address Wichita, KS 67202

Company to plug at: Hour: PM Day: 2 Month: 5 Year: 19 87

Plugging proposal received from W.C. Southmayd, Jr.

(company name) ONEOK Exploration Company (phone) _____

- were: 35 sacks cement at 4400'
- 35 sacks cement at 1000'
- 15 sacks cement at 40'
- 10 sacks cement in rathole
- 10 sacks cement in mousehole

Plugging Proposal Received by John Sanders
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: AM Day: 8 Month: 5 Year: 19 87

ACTUAL PLUGGING REPORT Fill hole with mud.

Pull pipe to 1125' and spot 35 sacks cement. Pull pipe to 320' and spot 35
sacks cement at 60' on bridge spot 25 sacks cement. Spot 10 sacks in rathole
and ten sacks in mousehole.

6-3-87

JUN 3 - 1987

Remarks: Halliburton #082021 60/40 6% gel.

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

INVOICED

(XXXX) (did not) observe this plugging.

DATE 6-3-87

Signed J.L. Sanders
(TECHNICIAN)

INV. NO. 17140