

2 040477

1-14

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 095-21,599 - 0000

SW NW NW, SEC. 5, T 27 S, R 8 W&E

4290 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6139

Lease Name Eberhardt Well # 1

Operator: Jay C. Boyer

County Kingman 122.53

Name & Address P. O. Box 511

Well Total Depth 3770 feet

Hays, KS 67601

Conductor Pipe: Size feet

913-625-6967

Surface Casing: Size 8-5/8 feet 229

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Duke Drilling License Number 5929

Address Great Bend KS

Company to plug at: Hour: Day: Month: Year: 19

Plugging proposal received from John Armbruster

(company name) Duke Drilling (phone)

were: 25 sx 1025'

25 sx 675'

35 sx 280'

25 sx 60' on plug

10 sx R.H.

Plugging Proposal Received by SVG (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None x

Operations Completed: Hour: 10:20 Day: 14 Month: 1 Year: 19 89

ACTUAL PLUGGING REPORT The drill was run to 1025' at base of salt and spotted 25 sx

of cement - the dp was pulled to top of salt at 625' where 25 sx of cmt was spotted

in place - the dp was pulled to 280', 50' below base of surface pipe where 35 sx

of cement was spotted - the dp was pulled from the hole and a plug was pushed to

60' and filled with cement to surface - the rat hole was circ. with

Remarks: 60/40 poz United Cementing

(if additional description is necessary, use BACK of this report)
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

(did or did not) observe this plugging.

DATE 2-3-89

Signed [Signature] (TECHNICIAN)

INV. NO. 23853