

1 031149

STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING SECTION
 200 COLORADO DERBY BUILDING
 WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 9740Operator: Petro Locators Inc.Name & Address Box 77Pratt, KS 67124-0077Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☐Other well as hereinafter indicated Plugging Contractor Bayse Well Servicing Company License Number 5670Address P.O. Box 149, Stafford, KS 67578Company to plug at: Hour: 8:30 a.m. Day: 9 Month: 3 Year: 19 91Plugging proposal received from Clarence Michael(company name) Petro Locators Inc. (phone) 316-672-3040were: 5½" at 3877', TOC 3100'1st plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"wiper plug and pump 100 sx cement.Plugging Proposal Received by Richard Lacey
(TECHNICIAN)Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐Operations Completed: Hour: 11:30 a.m. Day: 9 Month: 3 Year: 19 91ACTUAL PLUGGING REPORT 1st plug pumped through tubing at 929' with 4 sx hulls, 5 sx gel,and 50 sx cement, tagged cement at 718',2nd plug pulled tubing to 375', pumped 5 sx gel, 4 sx hulls, and circulated cement tosurface with 95 sx.RECEIVED
STATE CORPORATION COMMISSIONRemarks: Used 60/40 Pozmix 6% gel 3% cc by Allied. Recovered 2108' of 5½" casing.
(If additional description is necessary, use BACK of this form.) Wichita, Kansas

INVOICED

DATE 3-15-91INV. NO. 311873-9Signed Steve Shumant
(TECHNICIAN)FORM CP-2/3
Rev. 01-84

3-9
 API NUMBER 15- 185-01,042 . 00.01
 SE NE SE, SEC. 13, T 24 S, R 14 W/E
1650 feet from S section line
330 feet from E section line
 Lease Name Harrison Well # 2-13
 County Stafford 127.85
 Well Total Depth 3934 feet
 Conductor Pipe: Size feet
 Surface Casing: Size 8 5/8 feet 193