

15-095-21701-0000

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

10-8

2-070796

API Number: 15-095-21701000

C SW SW SECTION 18 TWP 27 RANGE 9 W

OPERATOR LICENSE #6236 660 FEET FROM S SECTION LINE
OPERATOR MTM 4620 FEET FROM E SECTION LINE
NAME & P.O. BOX 82
ADDRESS SPIVEY, KS 67142

LEASE NAME STEFFEN #1
COUNTY KINGMAN
WELL TOTAL DEPTH 4294'
PIPE 5 1/2" @ 4127 139.56
SURFACE CASING 8 5/8" @ 282'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: SHAWNEE WELL SERVICE

ADDRESS: P.O. BOX 333, ATTICA, KS 67009 LICENSE: 30346

COMPANY TO PLUG AT: HOUR: 12:00 DAY: 8 MONTH: 10 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM: JEFF CAPPS

COMPANY NAME: SHAWNEE WELL SERVICE PHONE: (316) 254-7893

WERE: CIBP - 3900 - 2 SACKS OF COMMON
35 SACKS @ 1450'
35 SACKS @ 950'
330' TO 0

10-19-98 RECEIVED
KANSAS CORPORATION COMMISSION
OCT 19 1998
CONSERVATION DIVISION
WICHITA, KS

PLUGGING PROPOSAL RECEIVED BY: JACK LUTHI

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL PART NONE

COMPLETED: HOUR: 5:00 DAY: 8 MONTH: 10 YEAR: 1998

ACTUAL PLUGGING REPORT: SET CIBP AT 3900' AND 2 SACKS OF COMMON. SHOT 5 1/2" CASING OFF AT 3450'.
PULLED TO 1450'. PUMPED 35 SACKS. PULLED TO 950'. PUMPED 35 SACKS. PULLED TO 330'. CIRCULATED
CEMENT TO SURFACE.

REMARKS: ALLIED #2579 - 60/40 POZ, 4% GEL

I DID OBSERVE THIS PLUGGING.

Jack Luthi
JACK LUTHI

FORM CP-2/3
REV. 3/90

10-20-98

60140