



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

JAN 23 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Percy Hall of Pickrell Drilling Co. has this date requested permission to plug the following described well:

Mr. Percy Hall guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Co.

Complete Address: 705 4th National Bk. Bldg., Wichita, Kansas

Lease Name: Sitts Well No. C # 1

Location: C SW NW Sec. 27 Twp. 27 Rge. 9 (E) (W) W

County Kingman Total Depth 4510 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Hall was instructed to plug the well as follows:

218' of 8 5/8" surface pipe circulated with 185 sacks cement. Fill hole with heavy mud to 180', 1/2 sack hulls, 1st cementing plug and 20 sacks cement; Fill hole with heavy mud to 40', 1/2 sack hulls, 2nd cementing plug and 10 sacks cemented to base of cellar. Rat hole bridged and cemented with 2 sacks.

Very truly yours,

Audie Elving
 Conservation Division Agent