

State of Kansas

FORM - CP-2



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

APR 12 1963  
4-12-63

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Bob Smith of Smith & Smith Casing Co. has this date requested permission to plug the following described well:

Mr. Smith guarantees payment of the plugging fee.

Operator's full Name: Texaco Inc.

Complete Address: 614 Bitting Bldg., Wichita, Kansas

Lease Name: Edith Hiebsch Well No. # 2

Location: NW NE SE Sec. 29 Twp. 29 Rge. 9 (E) (W) W

County Kingman Total Depth 4488 Oil Well     

Gas Well      Input Well      SWD Well X D & A      Lost Hole     

Mr. Smith was instructed to plug the well as follows:

372' of 8 5/8" surface pipe cement circulated with 220 sacks.  
Plugged back to 4322' cemented with 200 sacks. Top of cement  
3475'. Perferated at 4246'. Sand to 4230', cement with 5 sacks.  
Fill hole with mud to 200', 10' rock bridge, cement with 20  
sacks. Fill hole to 40', 10' rock Bridge cement with 10  
sacks to base cellar.

Very truly yours,

Arlie Elving  
 Conservation Division Agent