

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

NOV 15 1967
11-15-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Nov. 10, 1967.

Dear Sir:

Mr. Ralph Comstock of Comstock Pipe Pulling Inc has this date requested permission to plug the following described well:

Mr. Comstock guarantees payment of the plugging fee.

Operator's full Name: Skelly Oil Co.

Complete Address: 1860 Lincoln Street Denver, Colorado.

Lease Name: Cunningham B Well No. #30

Location: SW-NW-SW Sec 30 Twp 27 Rge 10W (E)(W)

County Kingman Total Depth 3462' Oil Well Abd.

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Comstock was instructed to plug the well as follows:

360' of 8 5/8" surface pipe circulated with 175 sacks
cement. 3407 ft. of 5 1/2" long string. Sand to 3375 ft. & 20
sacks cement. Mud to 320 ft. 10 ft. rock bridge, 25 sacks
cement. Mud to 40 ft., 10ft. rock bridge & 10 sacks cement
to surface. 2107 ft of 5 1/2" pipe pulled.

Very truly yours,

Harmon Justice
Conservation Division Agent