

State of Kansas



## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

WM. H. AVERY Governor  
 WILLIAM L. MITCHELL Chairman  
 JAMES O. GREENLEAF Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 NOV 13 1967  
 11-13-67  
 CONSERVATION DIVISION  
 WICHITA, KANSAS

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita 2, Kansas

Oct 31, 1967.

Dear Sir:

Mr. Ralph Comstock of Comstock Pipe Pulling Inc has this  
 date requested permission to plug the following described well:

Mr. Comstock guarantees payment of the plugging fee.

Operator's full Name: Skelly Oil Company

Complete Address: P.O. Box 649 McCook Nebraska.

Lease Name: Cunningham "B" Unit Well No. #39

Location: App. C-SW Sec. 30 Twp. 27 Rge. 10W (E)(W) W

County Kingman Total Depth 4016' Oil Well

Gas Well      Input Well X SWD Well      D & A      Lost Hole     

Mr. Comstock was instructed to plug the well as follows:

334' of 13 3/8" surface pipe circulated with 350 sacks  
cement. 4016' of 8 5/8" long string Top perforation at  
3490. Sand to 3450' & 20 sacks cement. Mud to 300 ft. & 10'  
rock bridge, 6 sacks cement (over-nite bridge) Hole bailed  
19 sacks cement. Mud to 40 ft. 10 ft. bridge & 20 sacks  
1000 ft. of 8 5/8" pulled.  
cement to surface.

Very truly yours,

Thurman Justus  
 Conservation Division Agent