

State of Kansas



WM. H. AVERY Governor
WILLIAM L. ANTCHELD Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. A. A. Lollar of Kewanee Oil Company has this
date requested permission to plug the following described well:

Mr. Lollar guarantees payment of the plugging fee.

Operator's full Name: Kewanee Oil Company

Complete Address: Box 2093, Wichita, Kansas

Lease Name: Barstow Well No. # 1

Location: 660' FWL 1980' FSL SW Sec. 5 Twp. 25 Rge. 15 (E)(W) W

County Stafford Total Depth 4340' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Lollar was instructed to plug the well as follows:

275' of 8 5/8" surface pipe, cement circulated with 225 sacks. Fill
hole with drilling mud to 240', 1st cementing plug, bridge with 1/2 sack
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION

JUL 19 1966

CONSERVATION DIVISION
Wichita, Kansas