

State of Kansas



FORM CP-2

JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

Dear Sir:

Mr. Buck Unruh of Kelso Casing Pulling has this date requested permission to plug the following described well:

Operator's Full Name: F.G.Holl

Complete Address: 6427 East Kellogg, Wichita, Kansas 67202

Lease Name: Cross Well No. 1-17

Location: 660' W C/EL Sec. 17 Twp. 24 Rge. 17W (E) (W)

County: Edwards Total Depth: 4493'

Abandoned Oil Well      Gas Well xx Input Well      SWD Well      D&A     

Other well as hereafter indicated:     

Mr. Buck Unruh was instructed to plug the well as follows:

275' of 8 5/8" SP W/240 sks

4 1/2" casing set @ 4490' W/325 sks

PB to 4358' Perf 4343'

Pumped bottom W/35 sks Pumped plug to 4000'

Pumped 15 gel 6 hulls 10 gel

Released plug & displaced @/125 sks 50/50 poz-mix 4% gel 3% cc

Recovered 4290' of 4 1/2" Very truly yours,

SIP 250# Cemented by Allied

[Signature]  
Conservation Division Agent

RECEIVED  
STATE CORPORATION COMMISSION

AUG 24 1981

8-24-81

CONSERVATION DIVISION  
Wichita, Kansas