

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 2/89

WELL PLUGGING APPLICATION FORM

(File One Copy)

15-151-102430000

API NUMBER 3-23-53 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR IUKA CARMI Development OPERATOR'S LICENSE NO. 31739 8/98

ADDRESS P.O. Box 847, Pratt, KS 67124-0847 PHONE # (316) 672-2531

LEASE (FARM) SICU WELL NO. 3/12 WELL LOCATION NW SW NW COUNTY Pratt

SEC. 18 TWP. 27S RGE. 12 (E) or (W) TOTAL DEPTH 4333' PLUG BACK TD 4329'

Check One:

OIL WELL X GAS WELL      D & A      SWD or INJ WELL      DOCKET NO.     

SURFACE CASING SIZE 8 5/8" SET AT 442' CEMENTED WITH 250 SACKS

CASING SIZE 5 1/2" SET AT 4333' CEMENTED WITH 200 SACKS

PERFORATED AT 4300' to 4311' And 4318' to 4323'

CONDITION OF WELL: GOOD      POOR      CASING LEAK      JUNK IN HOLE X

PROPOSED METHOD OF PLUGGING See Attached

6-24-98

RECEIVED  
KANSAS CORP COM  
JUN 24 11:11 AM '98

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED?      IS ACO-1 FILED?       
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN July 5, 1998 8:00am

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Ken Gates PHONE # (316) 672-2531

ADDRESS P.O. Box 847, Pratt, KS 67124-0847

PLUGGING CONTRACTOR Pratt Well Service LICENSE NO. 5056-5893 6/98

ADDRESS P.O. Box 847, Pratt, KS 67124-0847 PHONE # (316) 672-2531

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Richard A. Ferris  
(Operator or Agent)

DATE: 6-22-98

IUKA-CARMI Development, Inc.

SICU 3/12 (Burkner No. 3)  
NW SW NW, Sec. 18, T27S, R12W  
Pratt County, Kansas

Plugging and Abandonment Procedure

TD: 4333' PBTD: 4329' Elevation: 1887' BH 1895' KB

Surface Casing:

8-5/8" Set at 442' and cemented with 250 sacks.

Production Casing:

5-1/2" 14 & 17# set at 4333' and cemented with 200 sacks.

Perforations:

Upper Simpson	4300' to 4311'
Lower Simpson	4318' to 4323'

Hole Condition:

Verbal reports indicate a pump barrel, mud anchor, and a tubing anchor-catcher is at bottom of hole. The estimated length is approx. 90'.

Procedure

1. Move in and rig up well servicing unit.
2. Run in hole with sand pump on sand line and tag for bottom.  
(Use depthometer)
3. If tag up depth is close to perforations, spot sand to 50' above top perforation. (4300')
4. If tag depth significantly higher contact State Representative to obtain permission to set 25 sacks cement plug at tag up depth.
5. Pick up on 5-1/2" casing and determine free point from stretch. If casing free below anhydrite, cut casing and pull laying it down. (ANHYDRITE 1230' TO 1890')
6. If casing not free below anhydrite, perforate casing at bottom of anhydrite and squeeze with 50 sacks cement, leaving 25 inside 5-1/2" casing. Cut and pull 5-1/2" casing.
7. Spot a 50 sack cement plug at top of anhydrite or top of casing stub, which ever is shallowest.
8. Spot a 25 sack cement plug at surface casing shoe (442") and 10 sack surface plug.
9. Rig down well servicing unit. Cut off casing head and install a dry hole marker.
10. Reclaim surface location in accordance with surface owner.

RECEIVED  
KANSAS CORP. CO. #  
1998 JUN 24 AM 11:14



## Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Susan M. Seltsam, Commissioner Cynthia L. Claus, Commissioner

### NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

June 29, 1998

Iuka Carmi Development  
PO Box 847  
Pratt, Ks. 67124-0847

SICU #3-12  
API 15-15110243  
NW SW NW  
Sec. 18-27S-12W  
Pratt County

Dear Iuka Carmi Development,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely,

A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams  
Production Supervisor

District: #1  
304 W. McArtor  
Dodge City, KS 67801  
(316) 225-8888