

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

2-8-1971
RECEIVED
STATE CORPORATION COMMISSION
FFB 8 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Herren of H-30 Drlg. Co. Inc. has this date requested permission to plug the following described well:

Mr. Herren guarantees payment of the plugging fee.

Operator's full Name: Lee Brooks Oil Inc.

Complete Address: 918 Century Plaza Wichita, Ks

Lease Name: Fitzgerald Heirs Well No. 1

Location: C NW/NW/NE Sec. 33 Twp. 24 Rge. 13 (E)(W) W

County: Stafford Total Depth 4195 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Herren was instructed to plug the well as follows:

212 ft of 8 5/8 surface pipe cemented with 160 sacks. Pump
50 sacks cement to 800 ft. Fill hole to 350 ft, & pump
40 sacks cement. Mud to 40 ft, plug, 1/2 sack hulls, & 10
sacks cement to surface. 2 sacks cement in rat hole.

Halliburton Services Great Bend, Ks

Very truly yours,

A. Russell Bihirston
Conservation Division Agent