

State of Kansas

FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

MAR 14 1966

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Lee Paulsen of Tennaco Oil Company has this
date requested permission to plug the following described well:

Mr. Paulsen guarantees payment of the plugging fee.

Operator's full Name: Tennaco Oil Company

Complete Address: 2000 Classen Bldg., Oklahoma City, Okla.

Lease Name: C. E. Kirkpatrick Well No. # 21

Location: S~~W~~ S~~W~~ S~~E~~ Sec. 34 Twp. 24 Rge. 13 (E) (W) W

County Stafford Total Depth 3962' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Paulsen was instructed to plug the well as follows:

243' of 8 5/8" surface pipe, cement circulated with 225 sacks.

Fill hole with drilling mud to 225', 1st cementing plug, bridge

with hulls, and cement with 25 sacks. Fill hole with drilling mud

to 40', 2nd cementing plug, bridge with hulls, and cement with 10

sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,