

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

JUN 3 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Ralph Comstock of Comstock Pipe Pulling Co. has this
 date requested permission to plug the following described well:

Mr. Comstock guarantees payment of the plugging fee.

Operator's full Name: Rex & Morris Drilling Co. - Petroleum Inc.

Complete Address: P. O. Box 334, Eldorado, Kansas

Lease Name: Harter Well No. # 1

Location: NW SW NW Sec. 31 Twp. 24 Rge. 13 (E) (W) W

County Stafford Total Depth Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Comstock was instructed to plug the well as follows:

245' of 8 5/8" surface pipe, cement circulated with 250
sacks. 4138' of 4 1/2" long string, cemented with 100 sacks.
Perforated 4044' to 60'. Sand to 4030', cement with 3
sacks. Fill hole with mud to 225', 10' rock Bridge,
cement with 20 sacks. Fill hole with mud to 40', 10' rock
bridge, cement with 10 sacks to base cellar.

Very truly yours,

Archie Elving
 Conservation Division Agent