

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

12-5-64

RECEIVED  
STATE CORPORATION COMMISSION

DEC 5 1964

CONSERVATION DIVISION  
Wichita, Kansas

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY O. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Cal Roberts of Leben Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Roberts guarantees payment of the plugging fee.

Operator's full Name: Leben Drilling, Inc.

Complete Address: 815 Wichita Plaza, Wichita, Kansas

Lease Name: Dutton Well No. # 1

Location: C NW NE Sec. 21 Twp. 27 Rge. 8 (E)(W) W

County Kingman Total Depth 4445' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Roberts was instructed to plug the well as follows:

210' of 8 5/8" surface pipe, cement circulated with 275 sacks. Fill hole with drilling mud to 200', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls; and cement with 10 sacks to base of the cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent