

State of Kansas

FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Rec'd
 8-15-63

Dear Sir:

Mr. Ralph Watson of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Watson guarantees payment of the plugging fee.

Operator's full Name: Harvey Rosen

Complete Address: 701 Union Center, Wichita, Kansas

Lease Name: Lizzy Keller Well No. # 2

Location: NE NW NE Sec. 6 Twp. 27 Rge. 8 (E) (W) W

County Kingman Total Depth 4315 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Watson was instructed to plug the well as follows:

206' of 8 5/8" surface pipe, cement circulated. 4284' of
4 1/2" long string, cemented with 190 sacks. Sand to 4270',
cement with 3 sacks. Fill hole with mud to 260', 10' rock
bridge, cement with 25 sacks. Fill hole with mud to 40',
10' rock bridge, cement with 10 sacks to base cellar.

Very truly yours,

Archie Elving
 Conservation Division Agent