

State of Kansas



FORM - CP-2  
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

AUG 12 1963  
8-12-63  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Ralph Watson of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Watson guarantees payment of the plugging fee.

Operator's full Name: Harvey Rosen

Complete Address: 701 Union Center, Wichita, Kansas

Lease Name: Lizzy Kellar Well No. # 1

Location: NE NE NE Sec. 6 Twp. 27 Rge. 8 (E)(W)W

County Kingman Total Depth 4502 Oil Well

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Watson was instructed to plug the well as follows:

223' of 8 5/8" surface pipe, cement circulated. 4470' of  
5 1/2" long string, cemented with 100 sacks. Sand to 4460',  
cement with 5 sacks. Fill hole with mud to 250', 10' rock  
bridge, cement with 25 sacks. Fill hole with mud to 40',  
10' rock bridge, cement with 10 sacks to base cellar.

Very truly yours,

Archie Elving  
Conservation Division Agent