

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202
 RECEIVED
 STATE CORPORATION COMMISSION

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-185-21,327-0000

LEASE NAME Whitzel

WELL NUMBER #1

3630 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 7 TWP. 24 RGE. 15 (E) or (W)

COUNTY Stafford

Date Well Completed _____

Plugging Commenced 12-22-88

Plugging Completed 12-29-88

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR John O. Farmer, Inc.

ADDRESS Box 352, Russell, Kansas 67665

PHONE# 013-483-3144 OPERATORS LICENSE NO. 5135

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on December 21, 1988 (date)

by Richard Lacey and Steve Pfeiffer (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom T.D. 4130'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	303'	None
				4-1/2"	4129'	2,592.95'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same, and depth placed, from feet to feet each set. Allied squeezed off perforations with 100# hulls and 25 sacks common cement.

displaced plug to 3760' with 1500 psi. Shot casing at 3200' and 2900' & 2600' Pulled 68 joints of 4-1/2" casing. Allied plugged well with 400# hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 100# hulls, released plug and pumped 125 sacks 60/40

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111 over

Address Box 698, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: John O. Farmer, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold


James W. Rockhold

(Address) Box 698, Great Bend, Kansas 67530

SUBSCRIBED AND SWORN TO before me this 29th day of December, 19 88

Iona M. Leatherman
 Notary Public

My Commission Expires _____



pozmix cement with 6% gel. Maximum pressure was 400 psi and shutin 100 psi.