

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Stafford County. Sec. 10 Twp. 24S Rge. 15 ~~W~~ ~~W~~

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE SE NE

Lease Owner Vickers Explorations, Ltd.

Lease Name Nagel Well No. 1

Office Address Box 2240 Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed July 25 19 53

Application for plugging filed July 25 19 53

Application for plugging approved July 25 19 53

Plugging commenced July 25 19 53

Plugging completed July 25 19 53

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives Pratt, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4097 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	231	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled w/ mud to 225'. Set plug at 225'. Dump 20 sx. cement.  
Fill hole w/ mud to 35'. Set plug and dump 10 sx. cement.

08-08-53

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Jayhawk Drilling Co., Inc.

Address Box 2240 Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

John M. Little (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) *John M. Little*

Box 2240 Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 28 day of July, 1953

*Allen P. Denton*  
Notary Public.

My commission expires August 13, 1953



## VICKERS EXPLORATIONS, LTD.

Nagel, Well #1  
SE SE NE Sec. 10-24S-15W  
Stafford County, Kansas

Casing Record:  
8 5/8" @ 231' w/ 200 sx.

Commenced: July 8, 1953  
Completed: July 25, 1953

Elevation: 2027 R. B.  
D. & A.

LOG

Surface, Sand & Clay	0-231
Shale & Red Beds	231-420
Sand	420-470
Red Beds	470-945
Anhydrite	945-970
Shale	970-1550
Shale & Lime	1550-1775
Lime & Shale	1775-1885
Lime	1885-2015
Lime & Shale	2015-2095
Lime	2095-2405
Lime & Shale	2405-2990
Shale & Lime	2990-3195
Lime & Shale	3195-3295
Lime	3295-3464
Black Shale	3464-3470
Lime	3470-3474
Shale	3474-3482
Lime	3482-3500
Shale & Sandy Shale	3500-3598
Lime	3598-3602
Shale	3602-3606
Lime & Little Shale	3606-3962
Shale & Little Chert	3962-3999
Chert	3999-4017
Shale & Little Sand	4017-4032
Dolomite & Shale	4032-4060
Chert Quartz & Sand	4060-4095
Red Syenite	4095-4097 T. D.

L- DST 3777-80 Open 1 hr. Fair blow  
Recovered 3780' gas. 62' O & G  
cut mud. F.P.O# to 50# B.H.P. 1100#  
15 min, still building.

S- DST 4001-19 Open 45 min. Fair blow.  
Recovered 10' mud. VSRBSO F.P.12# to  
20#. B.H.P. 38# in 30 min.

S/A- DST 4007-37 Open 1 hr. Good blow.  
Recovered 35' mud. BHP 215# in 15 min.

A- DST 4037-47 Open 1 1/2 hr. Fair blow.  
Recovered 25' mud. FP 15# to 25#  
BHP 255# in 30 min.

DST 4037-97 Open 1 hr. Strong blow.  
Gas to surface 39 min. Too small to  
measure. Recovered 140' gas cut mud.  
BHP 545# in 15 min. Still building.

Sample Tops:

Heebner	3464
Toronto	3482
Douglas	3500
Brown Lime	3598
Lansing	3606
Conglomerate	3962
Viola	3999
Simpson	4017
Arbuckle	4032
Detrital Zone	4060
P. C. Syenite	4095

RECEIVED  
STATE CORPORATION COMMISSION  
AUG - 8 1953  
08-08-53  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that this Log is true and correct to the best of my knowledge and belief.

THE VICKERS EXPLORATIONS, LTD.

BY James T. Walker

Subscribed and sworn to before me this 3 day of August, 1953.

Allen P. Denton  
Notary Public

My Commission expires August 13, 1953.

