

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County. Sec. 9 Twp. 24 Rge. 15 (E) W (W)

Location as "NE/CNW&SW" or footage from lines SW SW NE

Lease Owner Fender Pipe & Supply, Inc.

Lease Name Petro Well No. 1

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced 10-16-65 19

Plugging completed 10-22-65 19

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Archie Elving

Producing formation Depth to top Bottom Total Depth of Well 4100 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	236'	None
				5-1/2"	4097'	2965'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to plug @ 3750', sanded hole to 3700' and dumped 5 sacks of cement @ 3700' with dump bailer. Pulled 5 1/2" casing, bailed hole down, set rock bridge @ 225' and set 1 sack of Cal Seal and dumped 3 sacks of cement. Bailed hole down and dumped 22 sacks of cement. Mudded hole to 40', set rock bridge and capped well with 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

OCT 28 1965
10-28-65

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY

Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss. Noel J. Knight

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight

Chase, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 27th day of October, 1965

Milton J. Volin

Notary Public.

My commission expires May 20, 1968

PETRO #1

15-185-01106-0000

Rex & Morris Drilling Company
and
Cooperative Refinery Association

Total Depth: 4104
Contractor: Rex & Morris Drilling Co.
Commenced: 8-21-60
Completed: 8-31-60
Initial Prod.: 23 BOPH

Location: SW SW NE
Section 9-24S-15W
Stafford County, Kansas

Casing Record:
8 5/8 @ 236' w/185 sacks
5 1/2 @ 4097 w/200 sacks

FORMATION	DEPTH
Surface Hole	236
Red Bed and Sand	965
Anhydrite	990
Shale and Shells	1825
Shale and Lime	2322
Lime and Shale	2740
Shale and Lime	2940
Lime and Shale	3060
Shale and Lime	3300
Lime	3440
Lime and Shale	3686
Lime	3989
Conglomerate	4001
Chert	4025
Shale	4038
Sand	4053
Sand and Shale	4080
Shale	4095
Lime T.D.	4100

R. U. S. T. and C. O. 4075
Perf. 6 shots per foot, 4034-42, 4045-50, 4054-57.
Test 35 C. O. P. H. Frac w/5000 gal. 7% acid
Gel and 10,000# sand. Flow 46 BO in 2 hrs.

9-8-65 - RUST & SWAB DOWN. SET BAKER BRIDGE PLUG
AT 3750', PERF 4 SHOTS PER FOOT 3719'-3722',
ACIDIZE 500 GAL 15% NE ACID, 104 BELS TOTAL
FLUID. SWAB DOWN & SWAB TEST 123 BELS WATER
& TRACE OIL. SHUT DOWN 12 HRS, SWABBED AND
TESTED 20.52 BELS WATER, 1.08 BELS OIL.

I hereby certify the foregoing statements are true and correct to the best
of my knowledge and belief.

Rex & Morris Drilling Company

By A. H. Fisher
A. H. FISHER

STATE OF KANSAS
COUNTY OF HUNTER, SS.

Subscribed and sworn to before me, a Notary Public, this 12th day of October,
1965.

Hazel N. Dilts
HAZEL N. DILTS, NOTARY PUBLIC

RECEIVED
STATE CORPORATION COMMISSION
OCT 14 1965
CONSERVATION DIVISION
Topeka, Kansas