


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Stafford County, Sec. 9 Twp. 24 Rge. 15 (E) W (W)
Location as "NE/CNW%SW%" or footage from lines SW NE NE
Lease Owner Fender Pipe & Supply, Inc.
Lease Name Petro Well No. 2
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19____
Application for plugging filed 19____
Application for plugging approved 19____
Plugging commenced 10-26-65 19____
Plugging completed 10-31-65 19____
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4105 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	226'	None
				4-1/2"	4105'	3246'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to cement plug @ 3545' previously set by Halliburton. Pulled 4 1/2" casing, set rock bridge @ 220' and dumped 5 sacks of cement on bridge. Bailed hole down and dumped 20 sacks of cement. Mudded hole to 40', set rock bridge to 30' and capped well with 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

NOV 9 1965
11-9-65

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 5th day of November, 1965

My commission expires May 20, 1968

Milton J. Volin
Notary Public.

WLB 7-25-
15-185-10486-0000

Elevation 2026 R.B.
2023 D.F.

PETRO #2

Rex & Morris Drilling Company
and
Cooperative Refinery Association

Total Depth: 4105
Contractor: Rex & Morris Drilling Co.
Commenced: 6-8-61
Completed: 6-18-61
Initial Prod.: Prod. Gas

Location: SW NE NE
Section 9-24S-15W
Stafford County, Kansas
Casing Record:
8 5/8 @ 226' w/190 sacks
4 1/2 @ 4105' w/100 sacks

FORMATION DEPTH

FORMATION	DEPTH
Surface Hole	226
Shale and Red Beds	955
Anhydrite	975
Shale and Salt	1215
Shale and Lime	1900
Lime and Shale	2525
Shale and Lime	2760
Lime and Shale	2955
Shale and Lime	3121
Lime and Shale	3315
Lime	3535
Lime and Shale	3644
Lime (K. C.)	3973
Lime and Shale	3979
Chert (Viola)	3997
Shale	4002
Shale and Sand	4053
Lime (Arbuckle) T.D.	4105

RECEIVED
STATE CORPORATION COMMISSION

OCT 14 1965

CONSERVATION DIVISION
STATE OF KANSAS

9-26-61 RUST, DP & CO, RAN GR-N LOG. ARBUCKLE 4046'
PERFORATED 4 JET SHOTS PER FOOT, 4046'-4063'
RAN TUBING & KICKED WELL OFF.

I hereby certify the foregoing statements are true and correct to the best of my knowledge and belief.

Rex & Morris Drilling Company

By Paul D. Koontz
Paul D. Koontz, Geologist

STATE OF KANSAS
COUNTY OF BUTLER, SS.

Subscribed and sworn to before me, a Notary Public, this 25th day of July, 1961.

Elizabeth Deschner
Elizabeth Deschner, Notary Public

My commission expires: August 8, 1962.