

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

MAY 23 1958
5-23-58

CONSERVATION DIVISION
Wichita, Kansas
NORTH

Stafford County, Sec. 8 Twp. 24 Rge. 15 (W)

Location as "NE/CNW%SW%" or footage from lines 660' N & 660' W of the SE 1/4

Lease Owner Columbia Supply Co.

Lease Name O'Conner Well No B-#1

Office Address East 10th, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed Yes 19

Application for plugging approved Yes 19


Plugging commenced 5-9 1958

Plugging completed 5-22 1958

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. Frank Broadfoot

Producing formation Depth to top Bottom Total Depth of Well 3892' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"		
				5 1/2"		2,212'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Measured into T.D. 3892'.

Plugging started 5-9-58. Finished 5-22-58.

Plugged off bottom with sand to 3700' and dumped 4 sacks cement.

Shot 5 1/2" casing at 2,212'. Circulated and spotted oil. Pulled pipe out of hole and squeezed well. Mixed and pumped in 15 sacks mud and 75 sacks cement. Capped well with 5 sacks cement. Well completed.

Name of Plugging Contractor (If additional description is necessary, use BACK of this sheet) J.O. Forbes d/b/a Forbes Casing Pulling Co.
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J.O. Forbes (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.O. Forbes
Box 221 Great Bend, Kans.
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of May, 1958

Betty S. Edman

Notary Public.

My commission expires November 8, 1960.

PLUGGING
FILE SEC 8 T 24 R 15W
BOOK PAGE 97 LINE 39

WELL RECORD MAY 23 1958

Sold to Columbia Supply Co.
Great Bend, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Company Ottawa Cement Co. Well No. 1 Farm O'Connor

Location 660' North and 660' West of NE Corner Sec. 8 T. 24 R. 15W

Elevation 2034 (2032 Cr.) County Stafford State Kansas

Drig. Comm. June 18, 1948 Contractor Corbett-Darbour Drilling Company

Drig. Comp. July 4, 1948 Acid 1000 gal. 3768-795 (7-14-48)
2500 gal. 3766-795 (7-20-48)

T. D. 4160' Initial Prod. Physical Potential: 54 oil, 222 water, 24 hrs. (6-17-48)
P.B.T.D. 3787' Lawrence-Kansas City

CASING RECORD:

8-5/8" 393' con. 250 sx con. and
3 sx C. C.
3-1/2" 3592' con. 150 sx con.

FORMATION RECORD:

clay & sand	0-75
shale	190
shale & shells	240
shale, shells & red bed	406
red bed & shale	810
shale & shells	960
anhydrite	990
shale & red bed	1000
shale & shells	1390
salt	1585
shale & shells	1700
lime	1790
lime & shale	1870
lime	1940
lime & shale	2110
shale & lime	2245
lime	2275
shale & lime	2300
lime	2575
shale & lime	2655
lime & shale	2820
shale & lime	2845
lime & shale	2940
lime	3005
shale & lime	3170
lime	4045
conglomerate	4058
chert & lime	4118
lime	4160 T. D.

Corr. Top Lansing	3645'
Top Cherty Conglomerate	4010'
Top Viola Chert	4058'
Top Simpson	4075'
Top Arbushlo	4118'
Penetration	42'
Total Depth	4160'

Drilled cement to 3855 DIM.

Perf. 12 shots 3800-19: 3-1/4
bailers water in 40 mins.

Corr. 36 shots 3766-795.
190' water w/ slight show oil in
1 hr. 25 mins.

Set Lane-wells plug at 3795;
dumped cement plug; top of cement
3787.

7-17-48 Shaped 40 oil, 41 wtr., 24 hrs.
7-23-48 Pumped 37 oil, 59 wtr., 22 hrs.

500'	1°
1000'	1°
1500'	0°
2000'	0°
2500'	1°
3000'	0°

RECEIVED

STATE CORPORATION COMMISSION

FEB 27 1958

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING

FILE SEC. 8 T. 24 R. 15W
BOOK PAGE 97 LINE 39

~~PLUGGING~~

FILE SEC. 8 T. 24 R. 15W
BOOK PAGE 95 LINE 29

Drill stem test 4119-25 recovered
30' mud in 30 mins.