


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Stafford County. Sec. 13 Twp. 24 Rge. (E) 14 (W)  
Location as "NE/CNW/SW" or footage from lines SE SE NE  
Lease Owner D. R. Lauck Oil Company, Inc.  
Lease Name Harrison Well No. 1  
Office Address 301 So. Broadway Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed June 2 19 59  
Application for plugging filed August 26 19 68  
Application for plugging approved August 28 19 68  
Plugging commenced September 11 19 68  
Plugging completed September 18 19 68  
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production August 20 19 68  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Ralph Warner  
Producing formation Mississippi Depth to top 3938 Bottom 3944 Total Depth of Well 4281 Feet  
Show depth and thickness of all water, oil and gas formations. PB 4221

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION   | CONTENT | FROM | TO   | SIZE         | PUT IN      | PULLED OUT   |
|-------------|---------|------|------|--------------|-------------|--------------|
| Mississippi | Oil     | 3938 | 3944 | 10 3/4<br>7" | 900<br>4243 | None<br>2453 |
|             |         |      |      |              |             |              |
|             |         |      |      |              |             |              |
|             |         |      |      |              |             |              |
|             |         |      |      |              |             |              |
|             |         |      |      |              |             |              |
|             |         |      |      |              |             |              |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sand 4221' to 3930'  
5 sacks cement 3930' to 3910'  
Plug 300'  
Rock Bridge 300' to 280'  
35 sacks cement 280' to 40'  
Rock & 15 sacks cement 40' to cellar base

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 3 - 1968  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Glenn & Smith Pipe Pulling Company  
Address Box 156 Ellinwood, Kansas 67526

STATE OF \_\_\_\_\_, COUNTY OF \_\_\_\_\_, ss.  
\_\_\_\_\_, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
P. O. Box 488 Ellinwood, Kansas 67526  
(Address)



FILED AND SWORN to before me this 30 day of September, 1968

March 6, 1972

Margaret E. Reusch  
Notary Public.

15-185-00256-0001

D R LAUCK OIL COMPANY

#1 HARRISON "A"

13-24-14W

SE SE NE

Contr. D R LAUCK

STAFFORD County

E 1928

Comm.

Comp. 7-3-59

IP

255 BOPD/FLO POT

OLD WELL WORK OVE

| Tops | Depth | Datum |
|------|-------|-------|
| HEEB | 3433  | -1505 |
| TOR  | 3451  | -1523 |
| DOUG | 3470  | -1542 |
| LANS | 3596  | -1668 |
|      |       |       |
| CONG | 3909  | -1981 |
| MISS | 3936  | -2008 |
| KIND | 3959  | -2031 |
| VIO  | 4018  | -2090 |
| SIMP | 4130  | -2202 |
| ARB  | 4182  | -2254 |
| TD   | 4220  | -2292 |

Casing ORIG COMP BY TEXAS CO AS D & A  
 10" 810 11-2-56  
 7" 4290  
 DST 3658-76/1 HR, 50' V SL GCM, 110' SW, BHP 1030#  
 DST 3739-51/1 HR, 20' GCM, 65' SW, BHP 590#  
 DST 3750-59/1 HR, 100' V H GC & SL GCM, 25' SW, BHP 520#  
 DST 3904-22/1 HR, 90' GCM, BHP 1085#

## NEW INFO:

DD 4290: 800' OIH: FRAC: FLO 71 BO/1ST HR  
 FLO 10 BO/9 HR

## RATTLESNAKE POOL

|   |   |   |
|---|---|---|
| + | + | + |
| + | + | + |
| + | + | + |

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

Original well log is not available due to the fact  
 that the Harrison "A" #1 well is an old well workover.

RECEIVED  
 STATE CORPORATION COMMISSION  
 AUG 28 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas