


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County, Sec. 14 Twp. 24S Rge. (E) 14 (W)
Location as "NE/CNW/SW" or footage from lines C SE SE NW
Lease Owner Abercrombie Drilling, Inc.
Lease Name MATHEWS Well No. 1
Office Address 801 Union Center, Wichita, Kansas, 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed April 5, 1964 19 64
Application for plugging filed verbally - April 4, 1964 19 64
Application for plugging approved verbally - April 4, 1964 19 64
Plugging commenced April 5, 1964 19 64
Plugging completed April 5, 1964 19 64
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? verbally - yes.

Name of Conservation Agent who supervised plugging of this well Archie Elving, Pratt, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4215 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	219'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 220'.
Set 1st plug at 220' w/25 sx cement & 1/4 sk hulls
Set 2nd plug at 40' w/10 sx cement & 1/4 sk hulls
Put 2 sx cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION

APR 9 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Abercrombie Drilling, Inc.
Address 801 Union Center, Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
I, B. Lynn Herrington, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) B. Lynn Herrington
801 Union Center, Wichita, Kansas,
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of April, 1964

My commission expires June 16, 1967

Leah Faye Herke
Leah Faye Herke
Notary Public.

CONTRACTOR'S WELL LOG

COMPANY: Abercrombie Drilling, Inc.
 CONTRACTOR: Abercrombie Drilling, Inc.
 FARM: MATHEWS #1
 LOCATION: SE SE NW Section 14-24S-14W
 Stafford County, Kansas
 COMMENCED: March 25, 1964
 COMPLETED: April 5, 1964

0	75	Sand
75	225	Shale
225	823	Red Bed
823	842	Anhydrite
842	950	Shale
950	1827	Shale & Shells
1827	3450	Lime & Shale
3450	3610	Lime
3610	3695	Lime & Shale
3695	4085	Lime
4085	4128	Viola
4128	4163	Viola Chert
4163	4201	Lime
4201	4215	Arbuckle
	4215	Rotary Total Depth

RECEIVED
 STATE CORPORATION COMMISSION

APR 9 1964

CONSERVATION DIVISION
 Wichita, Kansas

Set 8-5/8" Surface Casing at 219' with 200 sx cement, 2% CC.

DRY & ABANDONED

ELEVATION: 1933' K. B.

SAMPLE TOPS:

Heebner	3465'	(-1532)
Toronto	3485'	(-1552)
Douglas Shale	3502'	(-1569)
Brown Lime	3602'	(-1669)
Lansing/Kansas City	3629'	(-1696)
Viola	4018'	(-2085)
Simpson	4151'	(-2218)
Arbuckle	4201'	(-2268)

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, B. Lynn Herrington, do hereby certify that the above and foregoing is a true and correct copy of the log of the MATHEWS #1, SE SE NW, Section 14-24S-14W, Stafford County, Kansas, as reflected by the files of Abercrombie Drilling, Inc.

B. Lynn Herrington
 B. Lynn Herrington

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 8th day of April, 1964.

Leah Faye Henke
 Leah Faye Henke, Notary Public

My commission expires June 16, 1967.