


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Pitting Building
Wichita, Kansas

Stafford County. Sec. 14 Twp. 24S Rge. (E) 11 (W)
Location as "NE/CNW/SW" or footage from lines C E/2 E/2 SW/1
Lease Owner Greenland Drilling Company
Lease Name Neill Well No. 1
Office Address 506 Union Natl. Bank Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 1 - 6 19 56
Application for plugging filed 1 - 6 19 56
Application for plugging approved 1 - 6 19 56
Plugging commenced 1 - 6 19 56
Plugging completed 1 - 6 19 56
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage
Producing formation Depth to top Bottom Total Depth of Well 1220 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8" | 220' | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug at 245' with 25 sacks cement
Plug at 35' with 10 sacks cement
Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Greenland Drilling Company
Address 506 Union Natl. Bank Bldg., Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Richard S. Davis (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Richard S. Davis
Vice-President - 506 Union Natl. Bank Bldg.
(Address) Wichita 2, Kansas

SUBSCRIBED AND SWORN TO before me this 10th day of January, 19 56

Hedra B. Rutledge
Notary Public.

My commission expires March 15, 1956.

PLUGGING
FILE REC-14 LT 24 R 14W
BOOK PAGE 30 UNIT 14

JAN 11 1956
CONSERVATION DIVISION
Wichita, Kansas
1-11-56

WELL LOG

Company: GREENLAND DRILLING COMPANY

Sec. 14 Twp. 24S Rge. 14 W

Farm: NEILL No. 1

Location: E/2 E/2 SW/4
Stafford County, Kansas

Total Depth: 4220

Contractor: GREENLAND DRILLING COMPANY

Casing: 8-5/8" 220'
5-1/2" ---

Elevation: 1940 R.B.

Production: D & A


Figures Indicate Bottom of Formations

| | | | |
|------|------------------------|------------|------|
| 70 | Sand and clay | TOPS: | |
| 130 | Shale | Anhydrite | 825 |
| 220 | Shale & shells | Heebner | 3464 |
| 240 | Shale & shells | Brown Lime | 3591 |
| 560 | Red bed w/sand streaks | Lansing | 3616 |
| 825 | Red bed | Viola | 4060 |
| 846 | Anhydrite | Simpson | 4152 |
| 1350 | Shale & shells | Arbuckle | 4205 |
| 1550 | Shale & shells w/salt | TD | 4220 |
| 1875 | Shale & lime | | |
| 1990 | Lime | | |
| 2190 | Lime & shale | | |
| 2560 | Shale & lime | | |
| 2745 | Shale | | |
| 2900 | Shale & lime | | |
| 3015 | Lime & shale | | |
| 3047 | Shale | | |
| 3067 | Lime | | |
| 3080 | Shale & lime | | |
| 3150 | Lime & shale | | |
| 3190 | Shale & silt | | |
| 3250 | Lime & shale w/silt | | |
| 3300 | Lime | | |
| 3530 | Lime & shale | | |
| 3592 | Sandy shale & shale | | |
| 3595 | Lime | | |
| 3616 | Shale | | |
| 3672 | Lansing | | |
| 3965 | Lime | | |
| 3980 | Lime & shale | | |
| 4007 | Shale, lime & chert | | |
| 4040 | Chert, lime & shale | | |
| 4055 | Cherty lime | | |
| 4060 | Shale, lime & chert | | |
| 4096 | Viola chert | | |
| 4109 | Lime, cherty | | |
| 4127 | Chert & lime | | |
| 4146 | Lime & chert | | |
| 4152 | Lime | | |
| 4164 | Simpson | | |
| 4205 | Sand & shale | | |
| 4220 | Arbuckle lime | | |
| 4220 | T.D. | | |

1-11-56

STATE OF KANSAS, COUNTY OF SEDGWICK, s.s:

I, Richard S. Davis, of the Greenland Drilling Company, upon oath state that the above and foregoing is a true and correct copy of the log of the #1 Neill well.


Richard S. Davis, Vice-President

Subscribed and sworn to before me this 10th day of January, 1956.


Verdina B. Rutledge, Notary Public

My commission expires March 15, 1956.

