


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Stafford County, Sec. 14 Twp. 24S Rge. 14 (EX) (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines W SE SE
Lease Owner Hilton Drilling Company, Inc
Lease Name Miller B Well No. 1
Office Address 2421 Tenth Street, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed April 14, 19 54
Application for plugging filed June 12, 19 54
Application for plugging approved June 15, 19 54
Plugging commenced June 21, 19 54
Plugging completed June 25, 19 54

Reason for abandonment of well or producing formation commercially unproductive
If a producing well is abandoned, date of last production June 4, 19 54
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation Kansas City Depth to top _____ Bottom _____ Total Depth of Well 3975 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	213	8 5/8	213	None
		0	3974	5 1/2	3974	3105.7

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with crushed rock to 3660', pumped in 5 sacks cement.
Plugged surface with pump truck (Globe Cement Company), mixed and pumped in 25 sacks Gel Mud; put in plug.
Mixed and pumped in 68 sacks cement.
Shut well in.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ace Pipe Pulling Company
Address Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Henry Peacock, Secretary (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Henry Peacock Secretary
Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of July, 19 54

Armin Reinhard Leiber
Notary Public.

My commission expires January 26, 1955

24-7369-S 3-53-20M
PLUGGING
FILE SEC 14 T 24 R 14W
PAGE 41 LINE 5

RECEIVED
STATE CORPORATION COMMISSION
JUL 15 1954
7-12-54
CONSERVATION DIVISION
Wichita, Kansas

DRILLER'S LOG

COMPANY: Hilton Drilling Company, Inc. LOCATION: Center W/2 SE SE
 Section 14-24-14W
 CONTRACTOR: Hilton Drilling Company, Inc. Stafford County
 Kansas
 FARM NAME: MILLER "B" #1
 COMMENCED: April 1, 1954 ELEVATION: 1929 DF
 COMPLETED: April 14, 1954 CASING USED: 8-5/8" @ 213' w/200 sx.
 5-1/2" @ 3974' w/125 sx.

Sand and Clay	40
Sand	85
Clay, Streaks Sand	130
Shale	190
Red Bed	213
Red Bed & Blue Shale	285
Sand	320
Red Rock and Red Bed	585
Red Bed and Shale	795
Anhydrite	825
Red Bed and Shale	1260
Salt and Shale	1275
Salt and Shells, Shale	1625
Shale and Shells	1685
Bro. Lime and Shale	1815
Lime and Shale	1950
Lime	2030
Broken Lime and Shale	2175
Lime and shale	2775
Bro. Lime and shale	2920
Shale and Lime Streaks	3050
Shale and Lime	3135
Lime	3384
Lime and Shale	3440
Lime	3497
Shale and Lime	3583
Brown lime	3608
Lime - K. C.	3628
Lime	3852
Lime and Shale	3900
Cong. Shale, Lime	3950
Conglomerate	3967
Mississippi Lime and Chert	3975
T. D. (Total Depth)	3975

STATE OF KANSAS)
) ss.
 COUNTY OF BARTON)

7-12-54

I, the undersigned, being duly sworn on oath, state that the above statement and log are true and a correct record and log of the well drilled at the location above described.

PLUGGING
 W/2 SEC 14 T 24 N 14W
 ROCK FACE #1 LINE 5

HILTON DRILLING COMPANY, INC.
Henry Peacock
 Henry Peacock, Secretary

Subscribed and sworn to before me this 19th day of April, 1954.

Margaret Whitman
 Notary Public

My commission expires 4-4-56