

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-009-24,419-00-00

LEASE NAME Jennish

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 2

3860 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 16 TWP. 17 RGE. 12 (E) or (W)

COUNTY Barton

Date Well Completed 5-21-90

Plugging Commenced 5-21-90

Plugging Completed 5-22-90

LEASE OPERATOR Stepco Well Service, Inc.

ADDRESS P.O. Box 265 Ellinwood, KS 67526

PHONE#(316) 574-2909 OPERATORS LICENSE NO. 9764

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-18-90 (date)

by Bruce Basye (KCC District Agent's Name).

Is ACO-1 filed? operator to be filed by operator if not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 3428

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set

Bottom Plug: @ 3340' w/20 sacks cement thru drill pipe
Next Plug: @ 790' w/20 " " " " " 15 sacks in Rat Hole
Next Plug: @ 400' w/100 " " " " "
Top Plug: @ 40' w/10 " " " " "

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address P.O. Box 823 Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Stepco Well Service, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Leoanrd Willimason (Employee of Operator) or ~~XXXXXXXX~~ o
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts
statements, and matters herein contained and the log of the above-described well as filed that
the same are true and correct, so help me God.

(Signature) Leoanrd Willimason

(Address) P.O. Box 823 Great Bend, KS 675

SUBSCRIBED AND SWORN TO before me this _____ day of _____, 19 _____

KCC WICHITA

Notary Public

My Commission Expires: _____

MAR 21 2016

RECEIVED

DRILLER'S WELL LOG

DATE COMMENCED: May 16, 1990
DATE COMPLETED: May 22, 1990

Stepco Well Service, Inc.
JENNISE #2
100' S of E/2 W/2 NW
Sec. 16, T17S, R12W
Barton County, Ks.

ELEVATION: 1905 K.B.


0 - 773' Surface Soil, Shale, Sand Streaks
773 - 808' Anhydrite
808 - 2735' Shale & Lime
2735 - 3018' Lime
3018 - 3022' Shale
3022 - 3037' Lime & Shale
3037 - 3048' Lime
3048 - 3111' Shale
3111 - 3122' Lime & Shale
3122 - 3365' Lime
3365 - 3382' Lime & Shale
3382 - 3428' Dolomite
3428' RTD

Surface Pipe: Set used
8-5/8", 25# pipe @ 340'
w/160 sacks 50/50pozmix
2% gel 3% cc.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

Leonard Williamson of lawful age does swear and state that the facts and statements herein are true and correct to the best of his knowledge.



Subscribed and sworn to before me this _____ day of May 1990.

Notary Public

KCC WICHITA
MAR 21 2016
RECEIVED