

15-081-10122-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH

	X		

Locate well correctly on above
Section Plat

Haskell County. Sec. 17 Twp. 30 Rge. (E)33 (W)

Location as "NE/CNW/SW" or footage from lines 660' FNL & 1980' FWL

Lease Owner Amoco Production Co.

Lease Name Luciene Black "A" Well No. 2

Office Address P. O. Box 432 - Liberal, Ks. 67901

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed December 22, 19 61

Application for plugging filed July 10, 19 75

Application for plugging approved July 11, 19 75

Plugging commenced August 13, 19 75

Plugging completed August 14, 19 75

Reason for abandonment of well or producing formation Casing leak in the Glorietta Sand at approximately 1450'

If a producing well is abandoned, date of last production December 19 74

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence F. Thomas

Producing formation Lansing "B" Depth to top 4166' Bottom 4412' Total Depth of Well 4500' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Council Grove		2911		10-3/4	732	
Pennsylvania		3297		5-1/2	4505	1396
Missourian		4111				
Lansing "A"		4166				
Lansing "B"		4410				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sand from 4500' to 3800'. Oil, water, mud from 3800' to 1954'. Mud from 1954' to 737'. Cement from 737' to 637'. Mud from 637' to 30'. Cement from 30' to surface. CIBP set at 1954' with 2 sacks cement dumped on top.

RECEIVED
STATE CORPORATION COMMISSION

AUG 20 1975
8-20-75
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargent's Casing Pulling Service
Address 620 S. Lincoln - Liberal, Kansas 67901

STATE OF KANSAS, COUNTY OF SEWARD, ss.

F. J. Rader (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. J. RADER-Admn. Asst.

P. O. Box 432 - Liberal, Kansas 67901

(Address)

18th day of August, 1975

R. W. BANKS

R. W. BANKS
Notary Public.

