

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stafford County. Sec. 20 Twp. 24S Rge. 14W (E) (W)
Location as "NE/CNW/SW" or footage from lines NE NE NE

Lease Owner MORGENSTERN & SPECTER

Lease Name THUROW Well No. 1

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed 3-26-56 19

Application for plugging filed 5-4-64 19

Application for plugging approved 5-5-64 19


Plugging commenced May. 20. 1964 19

Plugging completed May. 25. 1964 19

Reason for abandonment of well or producing formation Failure to produce profitably.

If a producing well is abandoned, date of last production _____ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Archie V. Elving, Pratt, Kansas

Producing formation Arbuckle Depth to top 4309 Bottom 4310 1/2 Total Depth of Well 4315' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	235'	none
				5 1/2"	4310 1/2'	3205

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged, back with sand to 3580--feet, dumped 4- sacks cement.
Set a Rock Bridge at 230--feet, dumped 25- sacks cement.
Set a Rock Bridge at 35--feet, dumped ten sacks cement.

5-29-64

RECEIVED
STATE CORPORATION COMMISSION

MAY 29 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor LYNCH CASING PULLING COMPANY, NO. 457

Address R.Rt. 4 GREAT BEND, KANSAS

STATE OF Kansas, COUNTY OF Russell, ss.

Morgenstern & Specter (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of May, 19 64

My commission expires Dec 1, 1964

Notary Public: [Signature]

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-185-13176-0009


Apply to plug

Company- NATIONAL COOPERATIVE REFG. ASS'N
Farm- Thurow No. 1

SEC. 20 T. 24 R. 11W
NE NE NE

Total Depth. 4315'
Comm. 3-10-56 Comp. 3-26-56
Shot or Treated.
Contractor. Armer, Inc.
Issued. 4-6-57

County Stafford
KANSAS



CASING:
8" 235'
5" 4310 1/2'

Elevation. 1982' KB

Production. 116 BOPD

Figures indicate Bottom of Formations.

sand	150
shale-shells	235
red bed-shale	520
red bed-shells-sand	910
anhydrite	935
shale-shells	1100
shale-shells-sa lt	1550
shale-lime	2155
lime	2375
shale-lime	3394
lime	3480
lime-shale	3704
lime	4009
lime-shale	4055
cherty lime-shale	4098
lime-chert	4120
cherty lime	4125
shale-chert-lime	4165
lime-shale	4194
cherty lime-shale	4215
chert	4233
lime-shale	4315
Total Depth	

TOPS:	
anhydrite (scout)	910
Heebner	3518
Toronto	3538
Douglas	3556
Brown lime	3659
Lansing	3678
B/Kansas City	3923
Viola	4091
Simpson	4244 4344
Arbuckle	4309

RECEIVED
STATE CORPORATION COMMISSION

MAY 5 1964

CONSERVATION DIVISION
Wichita, Kansas