


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely.
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Stafford County. Sec. 20 Twp. 24 Rge. 14 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SW SE SW

Lease Owner Alpine Drilling Company
Lease Name Ulsh #1 Well No. _____
Office Address Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plot

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 2/17/78 _____ 19____
Plugging completed 3/30/78 _____ 19____
Reason for abandonment of well or producing formation
depleted. _____

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Owens
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4373
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	292	none
				5 1/2"	4372	3015

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pushed wood plug to 4075' and sanded to 4050', ran 5 sacks of cement. Shot pipe at 3510', 3222', 3017', pulled 90 joints. Pumped 3 sacks hulls, 25 sacks gel, released plug and pumped 125 sacks common cement with 2% gel and 3% cc.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
4-3-78
APR 03 1978

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of March, 19 78

My commission expires _____



Margaret Melcher
Notary Public.

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG ----- FRENDA ULSHE #1

Located: T1S SE 34, Section 20-24S-14W, Stafford
County, Kansas

OWNER: Alpine Drilling Company, Inc.
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: December 8, 1977
COMPLETED: December 19, 1977

TOTAL DEPTH: 4373'

<u>LOG</u>		<u>CASING RECORD</u>
0 - 295	Clay, Sand, Shale	Ran 7 joints 8 5/8" casing, 280' cemented at 292' K.B. with 225 sacks Common, 2% gal and 3% cc. Plug down at 2:00 AM, 12-9-77.
295 - 947	Shale	
945 - 968	Anhydrite	
968 - 1100	Red Bed - Shale	
1100 - 1975	Shale	
1975 - 2330	Lime and Shale	
2330 - 2550	Lime	
2550 - 3510	Lime and Shale	
3510 - 4160	Lime	
4160 - 4220	Lime and Shale	
4220 - 4373	Lime	Ran 129 joints 5 1/2" casing, 4373' set at 4372' K.B. with 125 sacks Common, 2% gel. Stage collar at 3243', pumped 20 bbl. oil and 50 sacks gel. Plug down at 1:30 AM, 12-19-77, by Allied.

STERLING DRILLING COMPANY
FEB 08 1978
CONTRACT NO. 1000000000