

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
NOV 29 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name D.R. Lauck Oil Co.
Complete Address 301 S Broadway Wichita, Ks
Lease Name Thurow Well No. 1
Location SE/SE/NW Sec. 16 Twp. 24 Rge. 14 (E) (W) W
County Stafford Total Depth 4303
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated _____
Plugging Contractor Glenn & Smith Pipe Pulling Co.
Address 204 E. 6th Ellinwood, Ks License No. 396
Operation Completed: Hour 12:00 Day 24 Month 11 Year 1971

The above well was plugged as follows:

206 ft 8 5/8 surface pipe cemented with 165 sacks. 4296 ft 5 1/2 long
string cemented with 125 sacks. Open hole. Sand back to 4200 ft,
5 sacks cement with bailer. Pulled 3100 ft 5 1/2. Pump 3 sacks hulls,
20 sacks gel, 100 sacks cement to surface.
Pumped by Globe Cementing Co. Great Bend, Ks

I hereby certify that the above well was plugged as herein stated.

Signed: A. Russell Bibeault
Well Plugging Supervisor

INVOICED

DATE 12-1-71
INV. NO. 4716-W