

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

OCT 17 1966
CONSERVATION DIVISION
Wichita, KansasJ. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasOperator's Full Name D. R. Lauck Oil Company, Inc. 10-17-1966Complete Address: 301 S. Broadway, Wichita, KansasLease Name Thurrow Well No. # 3Location SW SE NW Sec. 16 Twp. 24 Rge. 14 (E) (W) WCounty Stafford Total Depth 4315'Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Glen & Smith Casing Pulling CompanyAddress: Box 156, Ellinwood, Kansas License No. 396Operation Completed: Hour 10:45AM Day 13th Month Oct. Year 1966

The Above well was plugged as follows:

207' of 8 5/8" surface pipe, cement circulated. 4305' of 5 1/2" long string,
cemented with 125 sacks. This is an open hole. Bottom of the hole was sanded
to 4300', and cemented with 5 sacks. through the dump bailer. 2700' of 5 1/2"
long string was recovered from the hole. Hole had previously been mudded
through the annulus, and the hole was full of heavy drilling mud. 75 sacks
of cement was pumped into the surface pipe, through an 8 5/8" swage, squeez-
ing the hole to a pressure of 150 lbs. This cement was pumped by Glen &
Smith Casing Pulling Company.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging SupervisorDATE 10/17/66INV. NO. 4104-W