

KANSAS

 STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
OCT 19 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name D.R. Lauck Oil Co. Inc.

Complete Address 301 S. Broadway Wichita, Ks

Lease Name Smith Well No. 6

Location NE/SE/SW Sec. 16 Twp. 24 Rge. 14 (E) (W)

County Stafford Total Depth 4296

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Glenn & Smith Pipe Pullers

Address 204 E. 6th Ellinwood, Ks License No. 396


Operation Completed: Hour 2:00 PM Day 16 Month 10 Year 1970

The above well was plugged as follows:

205 ft of 8 5/8 surface pipe circulated. 4291 ft of 5 1/2 long string
cemented with 125 sacks. Open hole. Sand to 4280 ft, 5 sacks cement
with bailer. Pulled 3210 ft of 5 1/2. Pumped 1 sack hulls, 15 sacks
gel., 100 sacks cement to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: 
Well Plugging Supervisor

DATE 10-19-70

INV. NO. 2705-W