

Form CP-3  
Rev. 6-26-62

14  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

8-4-1965

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 4 - 1965  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Tom Lillard c/o Forbes Casing Pulling, Inc.

Complete Address: Box 221, Great Bend, Kansas

Lease Name Shell Well No. # 2

Location NW NE NW Sec. 13 Twp. 24 Rge. 14 (E) (W) W

County Stafford Total Depth 3844'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 1:45 PM Day 2nd Month August Year 1965

The Above well was plugged as follows:

910' of 8 5/8" surface pipe, cement circulated. 3844' of 5 1/2" long string,  
no record of cement. This is an open hole. Bottom of the hole was sanded  
to 3670', and cemented with 5 sacks. 2530' of 5 1/2" long string was recov-  
ered from the hole. Hole was filled with mud to 320', rock bridge from  
320' ot 300', and cemented with 25 sacks. Hole was filled with mud to  
40', rock bridged from 40' to 30', and cemented with 10 sacks to the  
base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving  
Well Plugging Supervisor

8/4/65  
1572-W