

KANSAS  
STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JUL 30 1965

CONSERVATION DIVISION  
Wichita, KansasJ. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, KansasOperator's Full Name Tom Lillard c/o Forbes Casing Pulling, Inc.Complete Address: Box 221, Great Bend, KansasLease Name Wise Well No. # 2Location SE NW NW Sec. 13 Twp. 24 Rge. 14 (E) (W) WCounty Stafford Total Depth 4205'Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A 

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Forbes Casing Pulling, Inc.Address: Box 221, Great Bend, Kansas License No. 49Operation Completed: Hour 11:00AM Day 29th Month July Year 1965

The Above well was plugged as follows:

835' of 8 5/8" surface pipe, cement circulated. 4203' of 5 1/2" long string,  
no record of cement. This was an open hole. Bottom of the hole was sanded  
to 4165, and cemented with 5 sacks. 2150' of 5 1/2" long string was recovered  
from the hole. Hole was filled with mud to 300', rock bridge from 300' to  
290', and cemented with 25 sacks. Hole was filled with mud to 40', rock  
bridge from 40' to 30', and cemented with 10 sacks to the base of the  
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7/30/65INV. NO. 1551-wSigned: Archie Elving  
Well Plugging Supervisor