

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 29 1964

CONSERVATION DIVISION
Wichita, KansasJ. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, KansasOperator's Full Name D. R. Lauck Oil Co., Inc.Complete Address: 301 South Broadway, Wichita, KansasLease Name Shell Well No. # 1Location NE SE SE Sec. 13 Twp. 24 Rge. 14 (E) (W) WCounty Stafford Total Depth 4007Abandoned Oil Well Gas Well X Input Well SWD Well D & AOther well as hereafter indicated: Plugging Contractor: Glen & Smith Casing Pulling Co.Address: 204 East Sixth, Ellinwood, Kansas License No. 396Operation Completed: Hour 10:30AM Day 27th Month July Year 1964

The Above well was plugged as follows:

225' of 8 5/8" surface pipe, cement circulated. 4007' of 5 1/2" long string,
cemented with 100 sacks. Plug back to 3963'. Top perforation 3910'. Bott-
om of the hole was sanded to 3900', and cemented with 5 sacks. Fluid lev-
el was up in the hole. Plug was pushed to 225', with 10' of rock bridge.
5 sacks of cement was mixed in barrel, and put on plug at 215', through
dump bailer, and let set over week end. Hole bailed down and 20 sacks of
cement was added to the plug. Hole was filled with mud to 40', and 10' of
rock bridge, cemented with 10 sacks to base of the cellar. 3487' of 5 1/2"
long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE

7/29/64

INV. NO.

9537-W

Signed:

Archie Elving
Well Plugging Supervisor