

Form CP-3  
Rev. 6-26-62

Y  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

APR 8 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Abercrombie Drilling Inc.

Complete Address: 801 Union Center, Wichita, Kansas

Lease Name Mathews Well No. # 1

Location SE SE NW Sec. 14 Twp. 24 Rge. 14 (E) (W) W

County Stafford Total Depth 4215

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A        X       

Other well as hereafter indicated:       

Plugging Contractor: Abercrombie Drilling Inc.

Address: 801 Union Center, Wichita, Kansas License No.       

Operation Completed: Hour 3:30AM Day 5th Month April Year 1964

The Above well was plugged as follows:

225' of 8 5/8" surface pipe, cemented with 150 sacks. Fluid level was  
up in the hole. Plug was pushed in fluid to 220', with 1/2 sack hulls,  
and cemented with 25 sacks, through the drill pipe. Hole was filled  
with drilling mud to 40', 2nd cementing plug, bridged with hulls, and  
cemented with 10 sacks to base cellar. Rat hole bridged and cemented  
with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INDEXED  
DATE 4/8/64  
INV. NO. 8899-W

Signed: Archie Elving  
Well Plugging Supervisor