

15-185-30087-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 10 1965

CONSERVATION DIVISION
Wichita, Kansas

8-16-1965

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Petroleum Inc.

Complete Address: 352 N. Broadway, Wichita, Kansas

Lease Name Neill "D" Well No. # 1

Location NW SE SW Sec. 14 Twp. 24 Rge. 14 (E) (W)W

County Stafford Total Depth 3619'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Garvey Drilling Company

Address: R. R. # 2, Great Bend, Kansas License No.

Operation Completed: Hour 7:15 AM Day 12th Month August Year 1965

The Above well was plugged as follows:

215' of 8 5/8" surface pipe, cement circulated with 250 sacks. Fluid
level was up in the hole. 1st cementing plug and 1/2 sacks of hulls was
pushed in fluid to 210', and cemented with 25 sacks, through the drill
pipe. Hole was filled with drilling mud to 40', 2nd cementing plug,
bridged solid with hulls on fluid at 40', and cemented with 10 sacks
to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/16/65

INV. NO. 1627-41

Signed: Archie Elving
Well Plugging Supervisor