

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasRECEIVED
STATE CORPORATION COMMISSIONMAY 26 1964
5-26-64
CONSERVATION DIVISION
Wichita, KansasOperator's Full Name Morgenstern & Spector Inc.Complete Address: P. O. Box 661, Russell, KansasLease Name Thurrow Well No. # 1Location NE NE NE Sec. 20 Twp. 24 Rge. 14 (E) (W) WCounty Stafford Total Depth 4315Abandoned Oil Well X Gas Well Input Well SWD Well D & A Other well as hereafter indicated: Plugging Contractor: Ralph Lynch Casing Pulling CompanyAddress: Route 4, Great Bend, Kansas License No. 457Operation Completed: Hour 11:00AM Day 25th Month May Year 1964

The Above well was plugged as follows:

235' of 8 5/8" surface pipe, cement circulated. 4315' of 5 1/2" long string,
cemented with 75 sacks. Top perforation 3592'. Plug was pushed to 3580',
with 10' of rock bridge, and bottom was cemented with 5 sacks. Fluid
level was up in the hole. Plug was pushed to 230', with 10' of rock and
sand bridge. 5 sacks of cement was mixed in barrel and put on plug, at
220', through the dump bailer, and let set over night. Next morning hole
bailed down, and 20 sacks of cement was added to the plug. Hole was fill-
ed with mud to 40', 10' of rock bridge, and cemented with 10 sacks to base
of cellar. 3200' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5/26/64INV. NO. 9201-WSigned: Archie Elving
Well Plugging Supervisor