

KANSAS

*Y*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 27 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Bovaird Supply Company

Complete Address: Box 358, Liberal, Kansas 67901

Lease Name Wall Well No. 3

Location C SE NE Sec. 35 Twp. 32 Rge. 23 (E) (W)

County Clark Total Depth 6640'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated: None

Plugging Contractor: Sargents Casing Pulling Co.

Address: Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 4:00PM Day 24 Month 8 Year 1968

The Above well was plugged as follows:

<u>8 5/8" to 584' circulated w/ cement.</u>	<u>4 1/2" to 6639' cemented.</u>
<u>Top perforations 4676'</u>	<u>Plug bottom w/ 20 sacks cement.</u>
<u>Top of cement 4400'</u>	<u>Mud 4400' to 584'</u>
<u>Spotted 35 sacks cement 584' to 484'</u>	<u>Mud 484' to 45'</u>
<u>Plug, Hulls &amp; 15 sacks cement 45' to 0'</u>	<u>Company Pump</u>
<u>Pulled 3803' of 4 1/2" casing.</u>	

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/27/68  
INV. NO. 8359-44

Signed: Edgar J. Eves  
Well Plugging Supervisor