

15-185-10476-0000

Form CP-3
Rev. 6-26-62

W
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

DEC 2 1963

12-2-63

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Santa Fe Pipe & Supply

Complete Address: P. O. Box 562, Great Bend, Kansas

Lease Name Eagan Well No. # 2

Location NE SE SW Sec. 36 Twp. 24 Rge. 14 (E) (W)

County Stafford Total Depth 4104

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractors: Ace Pipe Pulling Co.

Address: Box 304, Great Bend, Kansas License No. 2

Operation Completed: Hour 12:15PM Day 27th Month Nov. Year 1963

The Above well was plugged as follows:

327' of 8 5/8" surface pipe, cemented with 250 sacks. 4104' of 4 1/2" long
string, cemented with 50 sacks. Top perferation 4073'. Hole was sanded to
4060', and bottom cemented with 3 sacks. Water was flowing from hole and
a squeeze job was necessary. 15 sacks of mud-gel and 80 sacks cement,
with 2 sacks calcium chloride, was pumped into surface pipe, through an
8 5/8" swage, to a pressure of 150 lbs. The cementing was done by Ace
Pipe pulling Co.

3466' of 4 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 12/2/63

INV. NO. 8191-u