

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 9 1964

CONSERVATION DIVISION
Wichita, Kansas

1-9-64

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Frank J. Black

Complete Address: Box 150, McPherson, Kansas

Lease Name Howell Well No. # 1

Location SE NE SW Sec. 36 Twp. 24 Rge. 14 (E) (W) W

County Stafford Total Depth 4155

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 304, Chase, Kansas License No. 436

Operation Completed: Hour 4:30PM Day 4th Month Jan. Year 1964

The Above well was plugged as follows:

325' of 8 5/8" surface pipe, cemented with 200 sacks. 4100' of 5 1/2" long
string, this was squeezed through a Dakota hole at 800', and the pipe at
4100' had a partial collapse. 4150' of 3 1/2" was run inside of 5 1/2" long
string. CEMENTED WITH 30 SACKS Bottom of hole was sanded to 4140', and cemented with 4 sacks.
1st plug was set at 360', with 20' rock bridge, cemented with 20 sacks.
Hole was filled with mud to 40', 10' rock bridge, cemented with 10 sacks
to base cellar. 360' of 5 1/2" was recovered from the hole
3665' of 3 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 1/10/64

INV. NO. 8436-W