

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 11 1965
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Northeastern Petroleum Company

Complete Address: 2400 N. Main St., Hutchinson, Kansas

Lease Name Waters "B" Well No. # 1

Location C SE NE Sec. 32 Twp. 24 Rge. 14 (E) (W)W

County Stafford Total Depth 4215'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Northeastern Drilling Company

Address: 2400 N. Main St., Hutchinson, Kansas License No. _____

Operation Completed: Hour 5:15 PM Day 10th Month May Year 1965

The Above well was plugged as follows:

275' of 8 5/8" surface pipe, cement circulated with 230 sacks. Fluid
level in the hole was at 50'. 1st cementing plug and 1/2 sack of hulls
was pushed in fluid to 240', and cemented with 25 sacks, through the
drill pipe. Fluid level in the hole was now at 38', 1st cementing
plug, bridged solid with dry cement and hulls on fluid at 38', and
cemented with 10 sacks to the base of the cellar. Rat hole bridged
and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 5/11/65
1149-w

Signed: Archie Elving
Well Plugging Supervisor