

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JUL 8 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name D. R. Lauck Oil Company, Inc.

Complete Address: 301 South Broadway, Wichita, Kansas

Lease Name Smith Well No. # 8

Location NE NW SW Sec. 16 Twp. 24 Rge. 14 (E) (W) W

County Stafford Total Depth 4299

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Glen & Smith Casing Pulling Company

Address: 204 East Sixth, Ellinwood, Kansas License No. 396

Operation Completed: Hour 12:30PM Day 7th Month July Year 1964

The Above well was plugged as follows:

209' of 8 5/8" surface pipe, cement circulated. 4294' of 5 1/2" long string,  
cemented with 100 sacks. Bottom of the hole was sanded to 4280, and cem-  
ented with 5 sacks. Fluid level was up in the hole. Plug was pushed to  
200', and bridged with 10' of rock. 6 sacks of cement was mixed in the  
barrel, and put on plug through the dump bailer, and let set over-night.  
Next morning hole bailed down, 19 sacks of cement was added to the plug.  
Hole was filled with mud to 40', bridged with 10' of rock, and cemented  
with 10 sacks to base of the cellar. 3300' of 5 1/2" long string was recov-  
ered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elwing  
Well Plugging Supervisor

DATE 7/8/64

INV. NO. 9425-W