

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUN 27 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Mahoney of Amarillo Nat. Gas Co. has this
date requested permission to plug the following described well:

Mr. Mahoney guarantees payment of the plugging fee.

Operator's full Name: Amarillo Natural Gas Company

Complete Address: 305 Bank of southwest, Amarillo, Texas

Lease Name: Wall Well No. 2

Location: C SE SE Sec. 35 Twp. 32 Rge. 23 (E) (W) X

County Clark Total Depth 4455' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Mahoney was instructed to plug the well as follows:

8 5/8" to 571' circulated w/ cement, 4 1/2" to 4451' cemented

No perforations Plug bottom w/ 15 sacks cement

Top of cement 3232' Mud 2232' to 550'

Spotted 40 sacks cement 550' to 450' Mud 450' to 40'

Plug, Hulls & 10 sacks cement 40' to 0'

Very truly yours,

Edward J. Eves
Conservation Division Agent