



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 28 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Clift of Amerex has this

date requested permission to plug the following described well:

Mr. Clift guarantees payment of the plugging fee.

Operator's full Name: Amerex Inc.

Complete Address: 2000 Classen Bldg., Oklahoma City, Oklahoma

Lease Name: Abell Well No. 1-AA

Location: 1260 SNL P 760 WEL SW 1/4
1250' FSL & 760' FWL Sec. 35 Twp. 32 Rge. 23 (EX(W))

County: Clark Total Depth 4500' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Clift was instructed to plug the well as follows:

13 3/8" to 304' circulated w/ cement. 8 5/8" to 608' circulated w/ cement.


4 1/2" to 4500' Top perforation 4459'

Plug bottom w/ 25 sacks cement Top of cement 4000'

Mud 4000' to 600' Spot ~~120~~ 40 sacks cement 600' to 0'.

Spot 120 sacks cement 600' to 0' between 8 5/8" and 4 1/2".

Very truly yours,


Conservation Division Agent