

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

NOV 22 1966

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Mahoney of Amarillo Nat. Gas Co. has this  
date requested permission to plug the following described well:

Mr. Mahoney guarantees payment of the plugging fee.

Operator's full Name: Amarillo Natural Gas Company

Complete Address: 305 Bank of southwest Building, Amarillo Texas

Lease Name: Abell "A" Well No. 1

Location: G SE SW Sec. 35 Twp. 32 Rge. 23 W (W)

County Clark Total Depth 4750' Oil Well E

Gas Well    Input Well    SWD Well    D & A X Lost Hole   

Mr. Mahoney was instructed to plug the well as follows:

8 5/8" to 568' circulated w/ cement. 4 1/2" to 4749' cemented

2" Upset Tubing to 4250' Top perforations 4458'

Plug bottom w/ 100 sacks cement Top of cement 2750'

Fluid 2750' to 700' 200 sacks cement 700' to 0'.

Very truly yours,

Edgar J. Eves  
Conservation Division Agent