

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION

JUN 27 1967

CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Mahoney of Amarillo Nat. Gas has this  
date requested permission to plug the following described well:

Mr. Mahoney guarantees payment of the plugging fee.

Operator's full Name: Amarillo Natural Gas Company

Complete Address: 305 Bank of southwest, Amarillo, Texas

Lease Name: Shrewder Well No. 1

Location: SE NW Sec. 35 Twp. 32 Rge. 23 (E) (W)

County Clark Total Depth 4540' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Mahoney was instructed to plug the well as follows:

8 5/8" to 575' circulated w/ cement. 4 1/2" to 4539' cemented

Top perforations 4444' Plug bottom w/ 10 sacks cement.

Top of cement 4200' Mud 4200' to 550'

Spotted 40 sacks cement 550' to 450' Mud 450' to 40'

Plug, Hulls & 10 sacks cement 40' to 0'

Very truly yours,

E. Edward Johnson  
Conservation Division Agent