

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202RECEIVED
STATE CORPORATION COMMISSION

SEP 29 1972

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Clift of Mallonee has this

date requested permission to plug the following described well:

Mr. Clift guarantees payment of the plugging fee.

Operator's full Name: Mallonee-Mahoney Inc.

Complete Address: 925 Sutton Place, Wichita, Kansas

Lease Name: Abell Well No. 6

Location: C NW SW Sec. 35 Twp. 32 Rge. 23 XX (E) (W)

County: Clark Total Depth 4519' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Clift was instructed to plug the well as follows:

8 5/8" to 583, circulated w/ cement. 4 1/2" to 4519' cemented.

Top perforations 4453' Plug bottom w/ 15 sacks cement.

Top of cement 4202' Mud 4202' to 500'

Spot 35 sacks cement 500' to 400' Mud 400' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent