

State of Kansas



15-185-20082-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

JAN 2 1968

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

Rec'd 1-2-68

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Intent to Drill,  
filed December 19, 1967.

Dear Sir:

Mr. Joe Gerritzen of Braden Drilling, Inc. has this  
date requested permission to plug the following described well:

Mr. Gerritzen guarantees payment of the plugging fee.

Operator's full Name: Braden Drilling, Inc.

Complete Address: 1620 Wichita Plaza Bldg., Wichita, Kansas 67202

Lease Name: Kachelman Well No. # 1

Location: C NE SW Sec. 34 Twp. 24 Rge. 14 (E)(W) W

County Stafford Total Depth 3754' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Gerritzen was instructed to plug the well as follows:

248' of 8 5/8" surface pipe, cement circulated with 300 sacks. Fill  
hole with drilling mud to 240', 1st cementing plug, bridge with 1/2 sack  
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',  
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10  
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent